


BRUHAT BANGALORE MAHANAGARA PALIKE**Yelahanka Zone, Electrical Division****Office of the Executive Engineer
Electrical Division, Yelahanka Zone****Schedule B****Name of work :-Detailed Estime for Providing and Fixing of LED Street Lights
Ward No-11 in Byatarayanapura Division.**

Sl No	Qty	Description Of Work	Unit	Approved Rates	
				In figures	In words
1	52	LED Street light.Supply of LED Streetlight with pressure die cast aluminum housing body with optimal heat sink for better thermal dissipation. Diffuser with Injection moulded & is made of polycarbonate material with high transmission index, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%. CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains Current should not be greater than 0.1A to 0.7A & Surge Protection- Min 4KV along with Over voltage/Overload, short circuit/ miswiring protection. Compatible for pole mounting with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Over load & Short circuit protection ensures reliable operation in spite of problem in output side. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with W System Power consumption. LED Efficiency>130lm/w at 1W & Fixture Efficiency >80lm/w with nominal CRI >75. Luminaire manufacturer should have in-house facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008 . Housing with supplier word mark /name shall be Engraved / Embossing on the die cast housing/ Body part. Warranty of 5 Years against any manufacturing defect working under standard electrical conditions as mentioned above should be given by LED source manufacture. Suitable for B1/B2 Roads as per IS 1944 Part I & Part II.LED Streetlight 65watts	each	11000.00	Rupees Eleven Thousand only
2	102	Supplying & fixing of 32 mm dia class A GI pipe bracket up to 2 mtrs long bent at suitable angle and fixing to this bracket 1x40/2x40 or rail or RCC pole/wall using suitable clamps, bolts, and nuts and wiring using suitable capacity wires complete. Using 32mm dia G.I pipe	Each	200.00	Rupees Two Hundred Only
3	540	Wiring for lighting / power circuit using one of pvc insulated 1100v grade stranded aluminum unsheathed wire single core cable in open or concealed system of wiring as per IS - 694 : 19904sq mm	Per Mtr	2.00	RupeesTwo Only
4	525	Supplying of 1.1KV grade Aerial Bunched Cable Stranded & Compacted Aluminum Phase Conductor, and Stranded Messenger Conductor with all aluminum Alloy, Phase Conductor is insulated with XLPE Compound, insulated Messenger with specified IS-14255:1995 & confirming to GTP of GROUP-A.2 X 16 + 1 X 25 SQ.MM	Per Mtr	50.00	Rupees Fifty Only



Executive Engineer
Electrical Division
Yelahanka Zone BBMP
Byatarayanapura, Bangalore-92

5	525	Stringing of 1.1kv LT Arial Bunched Cable, BESCOM SR	Per Mtr	10.00	Rupees Ten Only
6	6	Micro processor based electronic timer consisting of Display Unit(LCD), built in Real Time Clock (RTC) and keypad with option to operate relay/contacter in programmable mode (pre-defined ON/OFF time) or astronomical mode (based on sunset and sunrise depending on the latitude and longitude of the location of installation of Switch) or based on Intensity of natural light (lux level using IR sensor), built in software to select the mode of operation by the user	Each	7000.00	Rupees Seven Thousand Only
7	6	Supply and fixing of 4-pole power contactor with NO/NC contacts on existing wood / panel board using necessary bolts, nuts, washers and wiring etc., complete. d) 100-125 Amps	Each	7000.0	Rupees Seven Thousand Only
8	6	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and wiring complete as required. 40-63 Amps SP	Each	600.00	Rupees Six Hundred Only
9	20	Wiring for lighting/power circuit using one of PVC insulated 1100v grade, multis and Copper conductor single core cable in open or concealed system of wiring. I Group A Materials. g) 16 sqmm	Per Mtr	10.00	Rupees Ten Only
10	1350	Supplying and fixing hylum brand hand plastic sheet 3mm thick with necessary niches for fixing switches, regulators etc., and fixing on existing wood or metal box using N.F.screws.	SqCm	0.1	Rupees Zero and One Paise Only
11	220	Open Conduit System: Supplying heavy gauge PVC conduit pipe, dia confirming to IS 2509 with suitable size bends, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall stone structure or plug in case of brick walls and cement plastering damaged portion using heavy gauge saddles at an interval of 700mm using NF screws. c) 32mm dia 2.5mm thick	Per Mtr	20.00	Rupees Twenty Only
12	19	Supplying and fixing angle iron frame work fabricated out of M.S angle iron... and M.S. flat... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint. a) 50X50X6 mm	mtr	50.00	Rupees Fifty Only
13	500	Supplying and stringing of ACSR Conductor (6/2.59mm Al + 1/2.59mm Steel).	Per Mtr	30.00	Rupees Thirty Only
14	15	1.1 KV Pin Insulator	Each	20.00	Rupees Twenty Only

15	15	2 Pin 45x45x5mm -510mm	Each	120.00	Rupees One Hundred and Twenty Only
16	6	Supply and installation /fixing/Provision of outdoor type thermoplastic modular panel enclosure with transparent polycarbonate lid, shock proof, IP 65(weather proof) rust proof, water proof, corrosin proof having internally embedded gasket on both id and flap suitable to fix. single phase/energy meter in suitable base plate and having a provision for fuse/ MCB cutout with suitable transparent hinged flap opening MCB along with complete tamper proof SEALING facility. 300x450x214mm.	Each	1500.00	Rupees One Thousand and Five Hundred Only
17	30	Supply and Installation / Fixing / Provision of Pole box with HRC Fuse / MCB provision and suitable connector / terminal for 3 Ph / 1 Ph connections with Loop-In & Loop-Out terminals for 10 Sqmm / 25 Sqmm 3.5 C Al/Ar / Cu/Ar Cable and branch out 2.5 Sqmm 2 core Al/Cu PVC Insulated cable, enclosed in a Thermoplastic, Polystyrene enclosure, which should be shock proof, safe, IP65(Weather Proof), rust proof, dust proof, water proof having Internally Embedded Gasket with provision for cable entry through IP65 Thermoplastic, polyamide glands and/or grommets.200mmx200mmx98mm	Each	1000.00	Rupees One Thousand Only
18	30	Supplying and fixing angle iron frame work fabricated out of M.S. angle iron.. And M.S. flat... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint. a)40X40X6mm	Per Mtr	20.00	Rupees Twenty Only
19	30	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete. Protection of Overload and Short circuit with thermal Magnetic/Micro processor release and Earth Fault as per IS-13947. (Icu = Ics) THREE POLE 100Amps25kA.	Each	8200.00	Rupees Eight Thousand Two Hundred Only
20	6	Supplying and running of GI/Copper strips for grounding connections, using necessary fixing materials as required. GI strip 25x3mm	Per Mtr	20.00	Rupees Twenty Only

For Chaitanya Electricals

Contractor

EXECUTIVE ENGINEER (ELEC)
BBMP, Yelahanka Zone